



# Advanced Membranes for VRFB. A Collaboration with SNL, PNNL and ORNL

September 28, 2012 Cy Fujimoto



Exceptional service in the

national

interest






## **Project**



- VRFB Proven technology;
   6MWh VRB on a 32 MW wind farm in Japan.
- Near Commercialization;
   Prudent Energy and UniEnergy
   Technologies
- Separation of energy and power
- At the electrodes only electron transport is occurs. Allows for deep discharge, long life cycles and little capacity fade




The problem is cost, DOE capital cost target \$100/kWh<sup>1</sup>
According to a recent study, current capital costs is \$380/kwh

#### Cost of VRFB

Base capital cost of VRFB, largest cost stems from vanadium. The stack costs is the second largest expense.

The membrane separator accounts for 40% of the cost of the stack.

Nafion<sup>™</sup> \$250-500/m<sup>2</sup> Perfluornated polymer (primarily C-F)



VRFB stack costs<sup>2</sup>

Developing hydrocarbon polymer (C-H) with equal or better performances to Nafion at a price target of \$40/m<sup>2</sup>

Sandia

## Membrane Considerations



#### Performance

- High current efficiency
- High voltage efficiency
- High energy efficiency [CE x VE = EE]

#### **Durability**

- Charge-Discharge cycles: >4,000 cycles
- Accelerated Durability: Vanadium +5 soaking studies


#### **Cost** [Membrane impacts more than material costs]

- More durable = Less maintenance
- More efficient = smaller stack

## Collaboration Structure:




To more effectively utilize our R&D resources by tasking each lab on their respective strengths and to prevent work duplication (leverage – no duplication)




### State of Hydrocarbon polymers in VRFB





Sulfonated arylene ether type polymers good EE, but there are durability problems; under 100 cycles

## Sandia Materials – <u>Diels Alder Polyphenylener National National Calder Polyphenylener Sandia Materials – Diels Alder Polyphenylener Sandia Materials – Diels Al</u>




- All poly(phenylene) backbone high chemicalthermal stability
- Membranes are flexible; poly(phenylene)s
   [PPP] are known for being brittle
- Ease of tailoring polymer backbone [cation exchange membrane]
- Donnan Exclusion: Fixed negative charges allow positive charge to pass

Membranes	Thickness*1 (mil)	IEC (meq/g)	Water uptake	D of V <sup>4+</sup> [cm²/min]	HFR <sup>*2</sup> (Ωcm²)
SDAPP 1.4	4.2	1.4	36%	4.4x10 <sup>-7</sup>	0.96
SDAPP 1.6	3.4	1.6	43%	8.1x10 <sup>-7</sup>	0.70
SDAPP 2.0	3.6	2.0	85%	4.3x10 <sup>-6</sup>	0.35
Nafion 117	7.0	0.99	35%	4.7x10 <sup>-6</sup>	0.84


<sup>5.</sup> C. Fujimoto, M. Hickner, C. Cornelius, D. Loy, Macromolecules, 38(12), 5010-5016, 2005

#### SDAPP VRFB Performance<sup>6</sup>





SDAPPs show slightly better EE



SDAPP1.4 shows stable EE even after +400hrs

SDAPP1.4 645 cycles (100d)



Very brittle HFR: 0.96→1.44Ωcm<sup>2</sup>

After +600 hrs SDAPP1.4 shows drop in performance

SDAPP slightly better EE than Nafion, longer cycle life than poly(arylene ether) however, +4,000 cycle lifetimes are required for VRFB

## **Durability Investigations**




Skyllas-Kazacos used ex-situ V<sup>+5</sup> soaking [0.1M] to gauge membrane lifetime

**V**+4 blue yellow time

Solution: 0.1M V<sup>5+</sup> + 5 M S, 40°C

Cycle number (until failure or performance changes)



Linear relationship between ex-situ in-situ data suggest that 300 days in V<sup>+5</sup> may simulate 4,000 cycles; more concentrated solutions should provide shorter time windows

Correlations between in situ and ex situ durability studies – able to approximate soaking times that would correspond to 4,000 cycles

#### **Conclusions:**



- Collaboration between the labs has been beneficial and has helped speed up R&D
- Hydrocarbon SDAPP have shown better performances than Nafion
- Typical hydrocarbon materials have show very low cyclic lifetimes (>100 cycles), however the SDAPP have shown +400 cycles
- Improvements still need to be made to reach +4,000 cycles

#### **Future:**

Understanding V+5 degradation mechanisms





- Mechanical
- Viscosity
- SEM





Also looking at IR and NMR, for mechanistic details

Improving DAPP oxidative resistance for longer lasting membranes



Thank you to Dr. Imre Gyuk and the Office of Electricity for funding support.